

PHILIPPINE BIDDING DOCUMENTS



Public Bidding for the Construction of Roxas City Riverside Promenade, Brgy. I, Roxas City under ITB No. RC- 2022-011i

Government of the Republic of the
Philippines

Sixth Edition
July 2020

TABLE OF CONTENTS

Glossary of Terms, Abbreviations, and Acronyms.....	4
Section I. Invitation to Bid	7
Section II. Instructions to Bidders.....	10
1. Scope of Bid.....	11
2. Funding Information	11
3. Bidding Requirements.....	11
4. Corrupt, Fraudulent, Collusive, Coercive, and Obstructive Practices	11
5. Eligible Bidders	12
6. Origin of Associated Goods	12
7. Subcontracts	12
8. Pre-Bid Conference	13
9. Clarification and Amendment of Bidding Documents	13
10. Documents Comprising the Bid: Eligibility and Technical Components.....	13
11. Documents Comprising the Bid: Financial Component.....	14
12. Alternative Bids	14
13. Bid Prices	14
14. Bid and Payment Currencies	14
15. Bid Security	14
16. Sealing and Marking of Bids	15
17. Deadline for Submission of Bids.....	15
18. Opening and Preliminary Examination of Bids	15
19. Detailed Evaluation and Comparison of Bids	15
20. Post Qualification	16
21. Signing of the Contract	16
Section III. Bid Data Sheet.....	17
Section IV. General Conditions of Contract	20
1. Scope of Contract	21
2. Sectional Completion of Works.....	21
3. Possession of Site.....	21
4. The Contractor's Obligations	21
5. Performance Security	22

6.	Site Investigation Reports	22
7.	Warranty	22
8.	Liability of the Contractor	22
9.	Termination for Other Causes.....	22
10.	Dayworks	23
11.	Program of Work.....	23
12.	Instructions, Inspections and Audits	23
13.	Advance Payment.....	23
14.	Progress Payments.....	24
15.	Operating and Maintenance Manuals.....	24
Section V. Special Conditions of Contract		25
Section VI. Specifications		27
Section VII. Drawings.....		31
Section VIII. Bill of Quantities		31
Section IX. Checklist of Technical and Financial Documents		35

Glossary of Terms, Abbreviations, and Acronyms

ABC – Approved Budget for the Contract.

ARCC – Allowable Range of Contract Cost.

BAC – Bids and Awards Committee.

Bid – A signed offer or proposal to undertake a contract submitted by a bidder in response to and in consonance with the requirements of the bidding documents. Also referred to as *Proposal* and *Tender*. (2016 revised IRR, Section 5[c])

Bidder – Refers to a contractor, manufacturer, supplier, distributor and/or consultant who submits a bid in response to the requirements of the Bidding Documents. (2016 revised IRR, Section 5[d])

Bidding Documents – The documents issued by the Procuring Entity as the bases for bids, furnishing all information necessary for a prospective bidder to prepare a bid for the Goods, Infrastructure Projects, and/or Consulting Services required by the Procuring Entity. (2016 revised IRR, Section 5[e])

BIR – Bureau of Internal Revenue.

BSP – Bangko Sentral ng Pilipinas.

CDA – Cooperative Development Authority.

Consulting Services – Refer to services for Infrastructure Projects and other types of projects or activities of the GOP requiring adequate external technical and professional expertise that are beyond the capability and/or capacity of the GOP to undertake such as, but not limited to: (i) advisory and review services; (ii) pre-investment or feasibility studies; (iii) design; (iv) construction supervision; (v) management and related services; and (vi) other technical services or special studies. (2016 revised IRR, Section 5[i])

Contract – Refers to the agreement entered into between the Procuring Entity and the Supplier or Manufacturer or Distributor or Service Provider for procurement of Goods and Services; Contractor for Procurement of Infrastructure Projects; or Consultant or Consulting Firm for Procurement of Consulting Services; as the case may be, as recorded in the Contract Form signed by the parties, including all attachments and appendices thereto and all documents incorporated by reference therein.

Contractor – is a natural or juridical entity whose proposal was accepted by the Procuring Entity and to whom the Contract to execute the Work was awarded. Contractor as used in these Bidding Documents may likewise refer to a supplier, distributor, manufacturer, or consultant.

CPI – Consumer Price Index.

DOLE – Department of Labor and Employment.

DTI – Department of Trade and Industry.

Foreign-funded Procurement or Foreign-Assisted Project – Refers to procurement whose funding source is from a foreign government, foreign or international financing institution as specified in the Treaty or International or Executive Agreement. (2016 revised IRR, Section 5[b]).

GFI – Government Financial Institution.

GOCC – Government-owned and/or –controlled corporation.

Goods – Refer to all items, supplies, materials and general support services, except Consulting Services and Infrastructure Projects, which may be needed in the transaction of public businesses or in the pursuit of any government undertaking, project or activity, whether in the nature of equipment, furniture, stationery, materials for construction, or personal property of any kind, including non-personal or contractual services such as the repair and maintenance of equipment and furniture, as well as trucking, hauling, janitorial, security, and related or analogous services, as well as procurement of materials and supplies provided by the Procuring Entity for such services. The term “related” or “analogous services” shall include, but is not limited to, lease or purchase of office space, media advertisements, health maintenance services, and other services essential to the operation of the Procuring Entity. (2016 revised IRR, Section 5[r])

GOP – Government of the Philippines.

Infrastructure Projects – Include the construction, improvement, rehabilitation, demolition, repair, restoration or maintenance of roads and bridges, railways, airports, seaports, communication facilities, civil works components of information technology projects, irrigation, flood control and drainage, water supply, sanitation, sewerage and solid waste management systems, shore protection, energy/power and electrification facilities, national buildings, school buildings, hospital buildings, and other related construction projects of the government. Also referred to as *civil works or works*. (2016 revised IRR, Section 5[u])

LGUs – Local Government Units.

NFCC – Net Financial Contracting Capacity.

NGA – National Government Agency.

PCAB – Philippine Contractors Accreditation Board.

PhilGEPS - Philippine Government Electronic Procurement System.

Procurement Project – refers to a specific or identified procurement covering goods, infrastructure project or consulting services. A Procurement Project shall be described, detailed, and scheduled in the Project Procurement Management Plan prepared by

the agency which shall be consolidated in the procuring entity's Annual Procurement Plan. (GPPB Circular No. 06-2019 dated 17 July 2019)

PSA – Philippine Statistics Authority.

SEC – Securities and Exchange Commission.

SLCC – Single Largest Completed Contract.

UN – United Nations.

Section I. Invitation to Bid



Republic of the Philippines
CITY OF ROXAS
City Hall, Roxas City 5800
(036) 620-5220

BIDS AND AWARDS COMMITTEE OFFICE

Invitation to Bid for

Public Bidding for the Construction of Roxas City Riverside Promenade, Brgy. I, Roxas City under ITB No. RC-2022-011i

1. The *Roxas City Government*, through the *GOP-2022* intends to apply the sum of ***Five Million Eight Hundred Twenty-five Thousand Fifty-one Pesos and 82/100 (5,825,051.82)*** being the Approved Budget for the Contract (ABC) to payments under the contract for ***Public Bidding for the Construction of Roxas City Riverside Promenade, Brgy. I, Roxas City under ITB No. RC-2022-011i***. Bids received in excess of the ABC shall be automatically rejected at bid opening.
2. The *Roxas City Government* now invites bids for the above Procurement Project. Completion of the Works is required ***One Hundred (100) Calendar Days***.

Bidders should have completed a contract similar to the Project. The description of an eligible bidder is contained in the Bidding Documents, particularly, in Section II (Instructions to Bidders).
3. Bidding will be conducted through open competitive bidding procedures using non-discretionary "*pass/fail*" criterion as specified in the 2016 revised Implementing Rules and Regulations (IRR) of Republic Act (RA) No. 9184.
4. Interested bidders may obtain further information from *Roxas City Government* and inspect the Bidding Documents at the address given below from 8:00 a.m. to 5:00 p.m.
5. A complete set of Bidding Documents may be acquired by interested bidders on ***November 11, 2022 to December 1, 2022*** from given address and website/s below and upon payment of the applicable fee for the Bidding Documents, pursuant to the latest Guidelines issued by the GPPB, in the amount of ***Ten Thousand Pesos (Php10,000.00)***. The Procuring Entity shall allow the bidder to present its proof of payment for the fees ***to be presented in person***.
6. The *Roxas City Government* will hold a Pre-Bid Conference on ***November 18, 2022, 10:00 a.m.***, at ***2nd Floor – Conference Room, City Mayor's Office, Roxas City Government***, which shall be open to prospective bidders.

7. Bids must be duly received by the BAC Secretariat through manual submission at the office address as indicated below on or before **December 1, 2022 at 10:00 a.m.** Late bids shall not be accepted.
8. All bids must be accompanied by a bid security in any of the acceptable forms and in the amount stated in **ITB** Clause 15.
9. Bid opening shall be on **December 1, 2022 at 10:00 a.m.** at the given address below. Bids will be opened in the presence of the bidders' representatives who choose to attend the activity.
10. The *Roxas City Government* reserves the right to reject any and all bids, declare a failure of bidding, or not award the contract at any time prior to contract award in accordance with Sections 35.6 and 41 of the 2016 revised Implementing Rules and Regulations (IRR) of RA No. 9184, without thereby incurring any liability to the affected bidder or bidders.
11. For further information, please refer to:

*Megan G. Barrientos
BAC Office
Arzobispo St., Roxas City
bacroxascity19@gmail.com
(036) 620-5220*

12. You may visit the following websites:

For downloading of Bidding Documents: *PhilGEPS.gov.ph*

November 11, 2022

LORIE BELLE O. USISON
BAC Chairperson

Section II. Instructions to Bidders

1. Scope of Bid

The Procuring Entity, *Roxas City Government* invites Bids for ***Public Bidding for the Construction of Roxas City Riverside Promenade, Brgy. I, Roxas City under ITB No. RC-2022-011i.***

The Procurement Project (referred to herein as “Project”) is for the construction of Works, as described in Section VI (Specifications).

2. Funding Information

2.1. The GOP through the source of funding as indicated below for *GOP-2021* in the amount of ***Five Million Eight Hundred Twenty-five Thousand Fifty-one Pesos and 82/100 (5,825,051.82).***

2.2. The source of funding is:

LGUs, the Annual or Supplemental Budget, as approved by the Sanggunian.

3. Bidding Requirements

The Bidding for the Project shall be governed by all the provisions of RA No. 9184 and its 2016 revised IRR, including its Generic Procurement Manual and associated policies, rules and regulations as the primary source thereof, while the herein clauses shall serve as the secondary source thereof.

Any amendments made to the IRR and other GPPB issuances shall be applicable only to the ongoing posting, advertisement, or invitation to bid by the BAC through the issuance of a supplemental or bid bulletin.

The Bidder, by the act of submitting its Bid, shall be deemed to have inspected the site, determined the general characteristics of the contracted Works and the conditions for this Project, such as the location and the nature of the work; (b) climatic conditions; (c) transportation facilities; (c) nature and condition of the terrain, geological conditions at the site communication facilities, requirements, location and availability of construction aggregates and other materials, labor, water, electric power and access roads; and (d) other factors that may affect the cost, duration and execution or implementation of the contract, project, or work and examine all instructions, forms, terms, and project requirements in the Bidding Documents.

4. Corrupt, Fraudulent, Collusive, Coercive, and Obstructive Practices

The Procuring Entity, as well as the Bidders and Contractors, shall observe the highest standard of ethics during the procurement and execution of the contract. They or through an agent shall not engage in corrupt, fraudulent, collusive, coercive, and obstructive practices defined under Annex “I” of the

2016 revised IRR of RA No. 9184 or other integrity violations in competing for the Project.

5. Eligible Bidders

- 5.1. Only Bids of Bidders found to be legally, technically, and financially capable will be evaluated.
- 5.2. The Bidder must have an experience of having completed a Single Largest Completed Contract (SLCC) that is similar to this Project, equivalent to at least fifty percent (50%) of the ABC adjusted, if necessary, by the Bidder to current prices using the PSA's CPI, except under conditions provided for in Section 23.4.2.4 of the 2016 revised IRR of RA No. 9184.

A contract is considered to be "similar" to the contract to be bid if it has the major categories of work stated in the **BDS**.

- 5.3. For Foreign-funded Procurement, the Procuring Entity and the foreign government/foreign or international financing institution may agree on another track record requirement, as specified in the Bidding Document prepared for this purpose.
- 5.4. The Bidders shall comply with the eligibility criteria under Section 23.4.2 of the 2016 IRR of RA No. 9184.

6. Origin of Associated Goods

There is no restriction on the origin of Goods other than those prohibited by a decision of the UN Security Council taken under Chapter VII of the Charter of the UN.

7. Subcontracts

- 7.1. The Bidder may subcontract portions of the Project to the extent allowed by the Procuring Entity as stated herein, but in no case more than fifty percent (50%) of the Project.

The Procuring Entity has prescribed that:

- a. Subcontracting is not allowed.

- 7.1. Subcontracting of any portion of the Project does not relieve the Contractor of any liability or obligation under the Contract. The Supplier will be responsible for the acts, defaults, and negligence of any subcontractor, its agents, servants, or workmen as fully as if these were the Contractor's own acts, defaults, or negligence, or those of its agents, servants, or workmen.

8. Pre-Bid Conference

The Procuring Entity will hold a pre-bid conference for this Project on the specified date and time and either at its physical address as indicated in paragraph 6 of the **IB**.

9. Clarification and Amendment of Bidding Documents

Prospective bidders may request for clarification on and/or interpretation of any part of the Bidding Documents. Such requests must be in writing and received by the Procuring Entity, either at its given address or through electronic mail indicated in the **IB**, at least ten (10) calendar days before the deadline set for the submission and receipt of Bids.

10. Documents Comprising the Bid: Eligibility and Technical Components

- 10.1. The first envelope shall contain the eligibility and technical documents of the Bid as specified in **Section IX. Checklist of Technical and Financial Documents**.
- 10.2. If the eligibility requirements or statements, the bids, and all other documents for submission to the BAC are in foreign language other than English, it must be accompanied by a translation in English, which shall be authenticated by the appropriate Philippine foreign service establishment, post, or the equivalent office having jurisdiction over the foreign bidder's affairs in the Philippines. For Contracting Parties to the Apostille Convention, only the translated documents shall be authenticated through an apostille pursuant to GPPB Resolution No. 13-2019 dated 23 May 2019. The English translation shall govern, for purposes of interpretation of the bid.
- 10.3. A valid PCAB License is required, and in case of joint ventures, a valid special PCAB License, and registration for the type and cost of the contract for this Project. Any additional type of Contractor license or permit shall be indicated in the **BDS**.
- 10.4. A List of Contractor's key personnel (e.g., Project Manager, Project Engineers, Materials Engineers, and Foremen) assigned to the contract to be bid, with their complete qualification and experience data shall be provided. These key personnel must meet the required minimum years of experience set in the **BDS**.
- 10.5. A List of Contractor's major equipment units, which are owned, leased, and/or under purchase agreements, supported by proof of ownership, certification of availability of equipment from the equipment lessor/vendor for the duration of the project, as the case may be, must meet the minimum requirements for the contract set in the **BDS**.

11. Documents Comprising the Bid: Financial Component

- 11.1. The second bid envelope shall contain the financial documents for the Bid as specified in **Section IX. Checklist of Technical and Financial Documents**.
- 11.2. Any bid exceeding the ABC indicated in paragraph 1 of the **IB** shall not be accepted.
- 11.3. For Foreign-funded procurement, a ceiling may be applied to bid prices provided the conditions are met under Section 31.2 of the 2016 revised IRR of RA No. 9184.

12. Alternative Bids

Bidders shall submit offers that comply with the requirements of the Bidding Documents, including the basic technical design as indicated in the drawings and specifications. Unless there is a value engineering clause in the **BDS**, alternative Bids shall not be accepted.

13. Bid Prices

All bid prices for the given scope of work in the Project as awarded shall be considered as fixed prices, and therefore not subject to price escalation during contract implementation, except under extraordinary circumstances as determined by the NEDA and approved by the GPPB pursuant to the revised Guidelines for Contract Price Escalation guidelines.

14. Bid and Payment Currencies

- 14.1. Bid prices may be quoted in the local currency or tradeable currency accepted by the BSP at the discretion of the Bidder. However, for purposes of bid evaluation, Bids denominated in foreign currencies shall be converted to Philippine currency based on the exchange rate as published in the BSP reference rate bulletin on the day of the bid opening.
- 14.2. *Payment of the contract price shall be made in: Philippine Pesos.*

15. Bid Security

- 15.1. The Bidder shall submit a Bid Securing Declaration or any form of Bid Security in the amount indicated in the **BDS**, which shall be not less than the percentage of the ABC in accordance with the schedule in the **BDS**.
- 15.2. The Bid and bid security shall be valid until *[indicate date]*. Any bid not accompanied by an acceptable bid security shall be rejected by the Procuring Entity as non-responsive.

16. Sealing and Marking of Bids

Each Bidder shall submit one copy of the first and second components of its Bid.

The Procuring Entity may request additional hard copies and/or electronic copies of the Bid. However, failure of the Bidders to comply with the said request shall not be a ground for disqualification.

If the Procuring Entity allows the submission of bids through online submission to the given website or any other electronic means, the Bidder shall submit an electronic copy of its Bid, which must be digitally signed. An electronic copy that cannot be opened or is corrupted shall be considered non-responsive and, thus, automatically disqualified.

17. Deadline for Submission of Bids

The Bidders shall submit on the specified date and time and either at its physical address or through online submission as indicated in paragraph 7 of the **IB**.

18. Opening and Preliminary Examination of Bids

18.1. The BAC shall open the Bids in public at the time, on the date, and at the place specified in paragraph 9 of the **IB**. The Bidders' representatives who are present shall sign a register evidencing their attendance. In case videoconferencing, webcasting or other similar technologies will be used, attendance of participants shall likewise be recorded by the BAC Secretariat.

In case the Bids cannot be opened as scheduled due to justifiable reasons, the rescheduling requirements under Section 29 of the 2016 revised IRR of RA No. 9184 shall prevail.

18.2. The preliminary examination of Bids shall be governed by Section 30 of the 2016 revised IRR of RA No. 9184.

19. Detailed Evaluation and Comparison of Bids

19.1. The Procuring Entity's BAC shall immediately conduct a detailed evaluation of all Bids rated "*passed*" using non-discretionary pass/fail criteria. The BAC shall consider the conditions in the evaluation of Bids under Section 32.2 of 2016 revised IRR of RA No. 9184.

19.2. If the Project allows partial bids, all Bids and combinations of Bids as indicated in the **BDS** shall be received by the same deadline and opened and evaluated simultaneously so as to determine the Bid or combination of Bids offering the lowest calculated cost to the Procuring Entity. Bid Security as required by **ITB** Clause 16 shall be submitted for each contract (lot) separately.

19.3. In all cases, the NFCC computation pursuant to Section 23.4.2.6 of the 2016 revised IRR of RA No. 9184 must be sufficient for the total of the ABCs for all the lots participated in by the prospective Bidder.

20. Post Qualification

Within a non-extendible period of five (5) calendar days from receipt by the Bidder of the notice from the BAC that it submitted the Lowest Calculated Bid, the Bidder shall submit its latest income and business tax returns filed and paid through the BIR Electronic Filing and Payment System (eFPS), and other appropriate licenses and permits required by law and stated in the **BDS**.

21. Signing of the Contract

The documents required in Section 37.2 of the 2016 revised IRR of RA No. 9184 shall form part of the Contract. Additional Contract documents are indicated in the **BDS**.

Section III. Bid Data Sheet

Bid Data Sheet

ITB Clause			
5.2	For this purpose, contracts similar to the Project refer to Government / Private Contracts which have the same major categories of work, which shall be: Construction / Repair / Rehabilitation of Parks, Promenades, Foot walks and any related completed projects pertaining to the said project.		
7.1	Sub-contracting is not allowed.		
10.3	No further instructions		
10.4	The key personnel must meet the required minimum years of experience set below:		
	Key Personnel	General Experience	Relevant Experience
	Project Engineer	1 year	1 year
	Construction Foreman	1 year	1 year
	Skilled Workers	1 year	1 year
	Laborers	1 year	1 year
	Equipment Operator	1 year	1 year
10.5	The minimum major equipment requirements are the following: Equipment 2 One Bagger Concrete Mixer 1 Dump Truck 1 Water Truck 1 Loader 3 Jackhammer 2 Welding Machine		
12	Alternate Bids shall not be accepted.		
15.1	The bid security shall be in the form of a Bid Securing Declaration or any of the following forms and amounts: a. The amount of not less than 2% of the ABC, if bid security is in cash, cashier's/manager's check, bank draft/guarantee or irrevocable letter of credit; b. The amount of not less than 5% of the ABC, if bid security is in Surety Bond.		
19.2	Partial bids are not allowed.		
20	No further instructions		

21	Additional contract documents relevant to the Project that may be required by existing laws and/or the Procuring Entity, such as construction schedule and S-curve, manpower schedule, construction methods, equipment utilization schedule, construction safety and health program approved by the DOLE, and other acceptable tools of project scheduling.
----	---

Section IV. General Conditions of Contract

1. Scope of Contract

This Contract shall include all such items, although not specifically mentioned, that can be reasonably inferred as being required for its completion as if such items were expressly mentioned herein. All the provisions of RA No. 9184 and its 2016 revised IRR, including the Generic Procurement Manual, and associated issuances, constitute the primary source for the terms and conditions of the Contract, and thus, applicable in contract implementation. Herein clauses shall serve as the secondary source for the terms and conditions of the Contract.

This is without prejudice to Sections 74.1 and 74.2 of the 2016 revised IRR of RA No. 9184 allowing the GPPB to amend the IRR, which shall be applied to all procurement activities, the advertisement, posting, or invitation of which were issued after the effectivity of the said amendment.

2. Sectional Completion of Works

If sectional completion is specified in the **Special Conditions of Contract (SCC)**, references in the Conditions of Contract to the Works, the Completion Date, and the Intended Completion Date shall apply to any Section of the Works (other than references to the Completion Date and Intended Completion Date for the whole of the Works).

3. Possession of Site

3.1 The Procuring Entity shall give possession of all or parts of the Site to the Contractor based on the schedule of delivery indicated in the **SCC**, which corresponds to the execution of the Works. If the Contractor suffers delay or incurs cost from failure on the part of the Procuring Entity to give possession in accordance with the terms of this clause, the Procuring Entity's Representative shall give the Contractor a Contract Time Extension and certify such sum as fair to cover the cost incurred, which sum shall be paid by Procuring Entity.

3.2 If possession of a portion is not given by the above date, the Procuring Entity will be deemed to have delayed the start of the relevant activities. The resulting adjustments in contract time to address such delay may be addressed through contract extension provided under Annex "E" of the 2016 revised IRR of RA No. 9184.

4. The Contractor's Obligations

The Contractor shall employ the key personnel named in the Schedule of Key Personnel indicating their designation, in accordance with **ITB** Clause 10.3 and specified in the **BDS**, to carry out the supervision of the Works.

The Procuring Entity will approve any proposed replacement of key personnel only if their relevant qualifications and abilities are equal to or better than those of the personnel listed in the Schedule.

5. Performance Security

5.1. Within ten (10) calendar days from receipt of the Notice of Award from the Procuring Entity but in no case later than the signing of the contract by both parties, the successful Bidder shall furnish the performance security in any of the forms prescribed in Section 39 of the 2016 revised IRR.

5.2. The Contractor, by entering into the Contract with the Procuring Entity, acknowledges the right of the Procuring Entity to institute action pursuant to RA No. 3688 against any subcontractor be they an individual, firm, partnership, corporation, or association supplying the Contractor with labor, materials and/or equipment for the performance of this Contract.

6. Site Investigation Reports

The Contractor, in preparing the Bid, shall rely on any Site Investigation Reports referred to in the **SCC** supplemented by any information obtained by the Contractor.

7. Warranty

7.1. In case the Contractor fails to undertake the repair works under Section 62.2.2 of the 2016 revised IRR, the Procuring Entity shall forfeit its performance security, subject its property(ies) to attachment or garnishment proceedings, and perpetually disqualify it from participating in any public bidding. All payables of the GOP in his favor shall be offset to recover the costs.

7.2. The warranty against Structural Defects/Failures, except that occasioned-on force majeure, shall cover the period from the date of issuance of the Certificate of Final Acceptance by the Procuring Entity. Specific duration of the warranty is found in the **SCC**.

8. Liability of the Contractor

Subject to additional provisions, if any, set forth in the **SCC**, the Contractor's liability under this Contract shall be as provided by the laws of the Republic of the Philippines.

If the Contractor is a joint venture, all partners to the joint venture shall be jointly and severally liable to the Procuring Entity.

9. Termination for Other Causes

Contract termination shall be initiated in case it is determined *prima facie* by the Procuring Entity that the Contractor has engaged, before, or during the

implementation of the contract, in unlawful deeds and behaviors relative to contract acquisition and implementation, such as, but not limited to corrupt, fraudulent, collusive, coercive, and obstructive practices as stated in **ITB** Clause 4.

10. Dayworks

Subject to the guidelines on Variation Order in Annex “E” of the 2016 revised IRR of RA No. 9184, and if applicable as indicated in the **SCC**, the Dayworks rates in the Contractor’s Bid shall be used for small additional amounts of work only when the Procuring Entity’s Representative has given written instructions in advance for additional work to be paid for in that way.

11. Program of Work

11.1. The Contractor shall submit to the Procuring Entity’s Representative for approval the said Program of Work showing the general methods, arrangements, order, and timing for all the activities in the Works. The submissions of the Program of Work are indicated in the **SCC**.

11.2. The Contractor shall submit to the Procuring Entity’s Representative for approval an updated Program of Work at intervals no longer than the period stated in the **SCC**. If the Contractor does not submit an updated Program of Work within this period, the Procuring Entity’s Representative may withhold the amount stated in the **SCC** from the next payment certificate and continue to withhold this amount until the next payment after the date on which the overdue Program of Work has been submitted.

12. Instructions, Inspections and Audits

The Contractor shall permit the GOP or the Procuring Entity to inspect the Contractor’s accounts and records relating to the performance of the Contractor and to have them audited by auditors of the GOP or the Procuring Entity, as may be required.

13. Advance Payment

The Procuring Entity shall, upon a written request of the Contractor which shall be submitted as a Contract document, make an advance payment to the Contractor in an amount not exceeding fifteen percent (15%) of the total contract price, to be made in lump sum, or at the most two installments according to a schedule specified in the **SCC**, subject to the requirements in Annex “E” of the 2016 revised IRR of RA No. 9184.

14. Progress Payments

The Contractor may submit a request for payment for Work accomplished. Such requests for payment shall be verified and certified by the Procuring Entity's Representative/Project Engineer. Except as otherwise stipulated in the **SCC**, materials and equipment delivered on the site but not completely put in place shall not be included for payment.

15. Operating and Maintenance Manuals

- 15.1. If required, the Contractor will provide "as built" Drawings and/or operating and maintenance manuals as specified in the **SCC**.
- 15.2. If the Contractor does not provide the Drawings and/or manuals by the dates stated above, or they do not receive the Procuring Entity's Representative's approval, the Procuring Entity's Representative may withhold the amount stated in the **SCC** from payments due to the Contractor.

Section V. Special Conditions of Contract

Special Conditions of Contract

GCC Clause	
2	<i>No further instructions</i>
4.1	<i>No further instructions</i>
6	<i>No further instructions</i>
7.2	<i>In case of permanent structures, such as buildings of types 4 and 5 as classified under the National Building Code of the Philippines and other structures made of steel, iron, or concrete which comply with relevant structural codes (e.g., DPWH Standard Specifications), such as, but not limited to, steel/concrete bridges, flyovers, aircraft movement areas, ports, dams, tunnels, filtration and treatment plants, sewerage systems, power plants, transmission and communication towers, railway system, and other similar permanent structures: Fifteen (15) years.</i>
10	No dayworks are applicable to the contract.
11.1	The Contractor shall submit the Program of Work to the Procuring Entity's Representative within <i>10 calendar</i> days of delivery of the Notice of Award.
11.2	No further instructions
13	The amount of the advance payment is <i>15% of the total contract price and schedule of payment.</i>
14	<i>No further instructions</i>
15.1	<p>The date by which operating and maintenance manuals are required is <i>on the day of acceptance of the finished project</i></p> <p>The date by which "as built" drawings are required is <i>on the day of acceptance of the finished project.</i></p>

Section VI. Specifications

A. Project Description and Location

The Construction of Roxas City Riverside Promenade, Brgy. I, Roxas City, Capiz along the Panay River is an addition to the three previous riverside development projects creating urban green spaces in the city with the following scope of work:

I. Construction of Bunkhouse and Installation of Signage

The bunkhouse shall be built by the Contractor on an area to be approved by the Project Engineer in coordination with the Punong Barangay of Barangay I where the project is located.

A project signage shall also be provided and installed by the Contractor measuring 2400mm x 2400mm in a conspicuous place, the size and format of which shall be approved by the Project Engineer.

II. Removal/Demolition of Structures and Obstructions

The approved site development plan of the project shall be the basis for the determination of the area which has to be cleared of illegal structures and obstructions. Prior to such activity however, the Contractor together with the Project Engineer shall coordinate with the Punong Barangay. Protection of other structures, workmen, and other people from damage and injury shall be strictly observed.

Lines shall be accurately staked out and grades established, after which the Contractor shall secure the approval of the Project Engineer before any excavation work is commenced.

III. Structural Excavation

Excavations shall be to the depths indicated on the approved detailed plans and sections of the project. Excavations for footings and foundations carried below required depths shall be filled with concrete.

IV. Foot walk and Bike Lanes

Paving blocks measuring 100mmx200mmx50mm with a compressive strength of 3000 PSI shall be used for foot walk and bike lanes laid on well-compacted ground which are cleared from bush roots or vegetable matter and debris. Clean sand sourced from the river shall be used to achieve the required elevation uniform all throughout the foot walk and bike lanes and for proper drainage. The final design layout and choice of colors shall be approved by the Project Engineer. These paving blocks shall be bonded with concrete edging or curbs as shown on the plans.

V. Concrete Works

1. Conveying of concrete shall be from the mixer to form as rapidly as practicable by methods which will prevent segregation or loss of ingredients.
2. Concrete shall be worked readily into the corners and angles of the forms and around the reinforcement and embedded items without permitting the material to segregate. Concrete shall be deposited as close as possible to its final position in the form.
3. Concrete shall be placed before initial set has occurred and before it has contained its water content more than 45 minutes.
4. The concrete shall be consolidated with the aid of mechanical vibrating equipment or by hand-spading or tamping.
5. All concrete shall be moist cured for a period of not less than seven (7) consecutive days by an approved method or combinations to local conditions. The surface of the concrete shall be kept continuously wet by covering with burlap plastic or other approved materials thoroughly saturated with water and keeping covering wet spraying or intermittent spraying.
6. Concrete surfaces shall be plastered unless otherwise indicated. Exposed concrete surfaces shall be formed with plywood. After removal of forms, the surfaces shall be smoothened through to line and shall present a finished appearance except for minor defects which can be easily repaired by patching cement mortar, or can be ground to a smooth surface to remove all joint marks of the form work.

VI. Masonry Works

1. Materials

Concrete hollow blocks shall have a minimum face shell thickness of 0.10x0.20x0.40 and a minimum compressive strength Class "B" 350 PSI

2. Reinforcement shall be 10mm dia. deformed bars
3. Sand shall be river sand, well screened, clean, hard, free from loam, silt and other impurities.
4. Cement shall be standard Portland Cement ASTM C-150-68 Type I
5. Mortar shall be mixed 3 to 5 minutes in such quantities as needed for immediate use. Re-tampering shall not be permitted if mortar stiffens because of premature setting. Discard such materials as well as those which have not been used within one hour after mixing.
6. Proportioning of cement mortar shall be one (1) part Portland cement and two (2) parts sand by volume but not more than one-part Portland cement and three parts sand by volume.
7. All masonry shall be laid plumb, true to line, with level and accurately spaced courses, with each course breaking joint and with the source below. Bond shall be kept plumb throughout; corners and reveals shall be greater than 12% absorption shall be wet before laying. Work required to be built in with masonry including anchors; wall plugs and accessories shall be built in as the erection progresses.

VII. Steel Works (Includes Repair of Railing and Ramp Posts)

1. All materials and workmanship shall conform to the latest edition of American Institute of Steel Construction Manual unless otherwise shown or noted.
2. Galvanized iron pipes to be used shall be 1-1/4" dia. x 6.00M; schedule 40
3. Square tubes shall 1"x1"x 6.00Mx 1.50mm
4. All welds shall be #1300 welding rods and shall develop at least 100% of the strength of the connected members and shall be grind to a smooth finish.
5. All exposed steel members shall have at least two coats of zinc chromate primer paint.

VIII. Painting

All painting works for this project shall be done with the use of approved brands by the Project Engineer. Before any painting is done, all surfaces shall be cleaned, smoothened, and free from dust, dirt, grease, mortar, rust and other foreign substances and all parts where paint remover has been used shall be washed off with paint or lacquer thinner. All paints shall be spread evenly and carefully. No painting shall be done in extremely foggy or damp weather.

IX. Forms and False Works

The Contractor shall provide all forms and false works required for this project. All materials to be used shall be of approved quality and shall be fabricated as rigid as possible.

X. Landscaping

The Contractor shall supply properly balled royal palm and African talisay trees to be planted on at least a cubic meter of garden soil on every location and shall be maintained until established as indicated on the drawings: 60 pieces of Royal Palm trees with a minimum height of seven (7) feet; 65 pieces of African Talisay with a minimum height of seven (7) feet. Required doses of rooting hormone shall be applied to promote plant growth.

Other ornamental plants shall also supplied and installed such as 985 pieces of eugenia variegated plants, 240 pieces of picarra plants; 400 pieces of dwarf golden pandakaki plants and applied with liquid fertilizer or vermicast as needed.

A horticulturist shall be hired by the Contractor during the project implementation to supervise the landscaping to ensure that the plants and trees are properly installed and cultivated.


XI. Electrical Works

The Contractor shall supply and install 65 sets of classical lamp post with 100W led lights as shown on the approved plans. All materials needed for this project shall be supplied new and of high quality and suitable for the location and purpose. Materials shall be standard products of reputable Manufacturers.

XII. Disposal of Waste Materials

The Contractor shall be responsible for the disposal of all waste materials. Any excess material remaining after completion of the earth work shall be disposed of by hauling or spreading in nearby spoil areas designated by the Project Engineer. Excavated materials deposited in the spoil areas shall be graded to a uniform surface. All other residual wastes may be transported to the sanitary landfill at Barangay San Jose, Roxas City for disposal.

Section VII. Drawings



PERSPECTIVE



REPUBLIC OF THE PHILIPPINES
OFFICE OF THE CITY ENGINEER
CITY OF ROXAS


PROJECT TITLE:
ROXAS CITY RIVERSIDE PROMENADE,
BRYD L. LUNA NOWICID EXT., ROXAS CITY

DESIGNED BY:
ALFONSO H. BEDIONES IV
ARCHITECTURAL DESIGNER


ENGINEER BY:
FRANCIS FERNANDO A. BILLONES
ENGINEER IV

CHECKED BY:
ANTONIO V. AMOROSO, JR.
CITY ENGINEER


APPROVED BY:
HON. RONNIE T. DADIVAS
CITY MAYOR



LOCATION PLAN
SCALE: NTS



PROMENADE TYPICAL PLAN
SCALE: NTS



TYPICAL RAILING DESIGN
SCALE: NTS



REPUBLIC OF THE PHILIPPINES
OFFICE OF THE CITY ENGINEER
CITY OF ROXAS



PROJECT TITLE:
ROXAS CITY RIVERSIDE PROMENADE,
BRYD L. LUNA NOWICID EXT., ROXAS CITY


DESIGNED BY:
ALFONSO H. BEDIONES IV
ARCHITECTURAL DESIGNER

ENGINEER BY:
FRANCIS FERNANDO A. BILLONES
ENGINEER IV

CHECKED BY:
ANTONIO V. AMOROSO, JR.
CITY ENGINEER

APPROVED BY:
HON. RONNIE T. DADIVAS
CITY MAYOR





Section VIII. Bill of Quantities

Public Bidding for the Construction of Roxas City Riverside Promenade, Brgy. I, Roxas City under ITB No. RC-2022-011i

Item No.	Item Description	QTY	UOM	Unit Cost	Total Cost
1	CONSTRUCTION OF BUNKHOUSE	64	SQ.M		
2	PROJECT BILLBOARD / SIGNBOARD	2	EA		
3	REMOVAL OF DEMOLITION STRUCTURES / OBSTRUCTIONS	1	LOT		
4	EXCAVATION	94.5	CU.M		
5	CONCRETE WORKS	107.69	CU.M		
6	REINFORCING STEELWORKS	10,916	KGS		
7	FORMWORKS & FALSEWORKS	642.6	SQ.M		
8	PAVED BLOCKS	333	SQ.M		
9	MASONRY WORKS	133.36	SQ.M		
10	PLASTERING	282.16	SQ.M		
11	RAILINGS	111	LN.M		
12	PAINTING WORKS	364.1558	SQ.M		
13	ELECTRICAL WORKS	1	LOT		
14	LANDSCAPING	333	SQ.M		
15	DISPOSAL OF WASTE MATERIALS	1	LOT		
TOTAL					

Name of Bidder _____.

[signature]

[in the capacity of]

Duly authorized to sign Bid for and on behalf of _____

Section IX. Checklist of Technical and Financial Documents

Checklist of Technical and Financial Documents

I. TECHNICAL COMPONENT ENVELOPE

Class "A" Documents

Legal Documents

- ☐ (a) Valid PhilGEPS Registration Certificate (Platinum Membership) (all pages);
or
- ☐ (b) Registration certificate from Securities and Exchange Commission (SEC), Department of Trade and Industry (DTI) for sole proprietorship, or Cooperative Development Authority (CDA) for cooperatives or its equivalent document;
and
- ☐ (c) Mayor's or Business permit issued by the city or municipality where the principal place of business of the prospective bidder is located, or the equivalent document for Exclusive Economic Zones or Areas;
and
- ☐ (e) Tax clearance per E.O. No. 398, s. 2005, as finally reviewed and approved by the Bureau of Internal Revenue (BIR).

Technical Documents

- ☐ (f) Statement of the prospective bidder of all its ongoing government and private contracts, including contracts awarded but not yet started, if any, whether similar or not similar in nature and complexity to the contract to be bid; **and**
- ☐ (g) Statement of the bidder's Single Largest Completed Contract (SLCC) similar to the contract to be bid, except under conditions provided under the rules; **and**
- ☐ (h) Philippine Contractors Accreditation Board (PCAB) License;
or
Special PCAB License in case of Joint Ventures;
and registration for the type and cost of the contract to be bid; **and**
- ☐ (i) Original copy of Bid Security. If in the form of a Surety Bond, submit also a certification issued by the Insurance Commission;
or
Original copy of Notarized Bid Securing Declaration; **and**
- ☐ (j) Project Requirements, which shall include the following:
 - ☐ a. Organizational chart for the contract to be bid;
 - ☐ b. List of contractor's key personnel (e.g., Project Manager, Project Engineers, Materials Engineers, and Foremen), to be assigned to the contract to be bid, with their complete qualification and experience data;
 - ☐ c. List of contractor's major equipment units, which are owned, leased, and/or under purchase agreements, supported by proof of ownership or certification of availability of equipment from the

- equipment lessor/vendor for the duration of the project, as the case may be; **and**
- ☐ (k) Original duly signed Omnibus Sworn Statement (OSS); **and** if applicable, Original Notarized Secretary's Certificate in case of a corporation, partnership, or cooperative; or Original Special Power of Attorney of all members of the joint venture giving full power and authority to its officer to sign the OSS and do acts to represent the Bidder.

Financial Documents

- ☐ (l) The prospective bidder's audited financial statements, showing, among others, the prospective bidder's total and current assets and liabilities, stamped "received" by the BIR or its duly accredited and authorized institutions, for the preceding calendar year which should not be earlier than two (2) years from the date of bid submission; **and**
- ☐ (m) The prospective bidder's computation of Net Financial Contracting Capacity (NFCC).

Class "B" Documents

- ☐ (n) If applicable, duly signed joint venture agreement (JVA) in accordance with RA No. 4566 and its IRR in case the joint venture is already in existence;
or
duly notarized statements from all the potential joint venture partners stating that they will enter into and abide by the provisions of the JVA in the instance that the bid is successful.

II. FINANCIAL COMPONENT ENVELOPE

- ☐ (o) Original of duly signed and accomplished Financial Bid Form; **and**

Other documentary requirements under RA No. 9184

- ☐ (p) Original of duly signed Bid Prices in the Bill of Quantities; **and**
- ☐ (q) Duly accomplished Detailed Estimates Form, including a summary sheet indicating the unit prices of construction materials, labor rates, and equipment rentals used in coming up with the Bid; **and**
- ☐ (r) Cash Flow by Quarter.

